



REBOUND ACE GS8

INSTALLATION SCHEDULE GUIDE

PROCESS	No. of Men for Process	No. of Days for Process				
		(including curing)				
		1 Court	2 Courts	3 Courts	4 Courts	6 Courts
1. Site set up/surface preparation	2	2	2	2	3	4
2. Adhesive/base mat	5	2.5	10	3	4	6
3. 1st Mat Sealer	2	1				
4. 2nd Mat Sealer	2	1	2	2	3	4
5. Polyvac Sand/Vacuum	1	0.5				
6. Tycoat/Fibreglass	3	1.5	1	3	4	6
7. 1st Filler Coat	2	1	1	2	2	3
8. 2nd Filler Coat	2	01				
9. Sand/Grind ridges	1	0.5	1	1	1	2
10. 1st Topcoat	2	1	2	2	2	3
11. 2nd Topcoat	2	1				
12. Linemarking	2	1	1	2	2	3
13. Site Clean up (progressive)	2	1				
Sub Total days		10	14	19	24	34
Number of man days		15	54	73	94	134
25% bad weather allowance		7	14	18	24	34
Total man days		19	68	91	118	168