

# REBOUND ACE HSA

## INSTALLATION SCHEDULE GUIDE

PROCESS	No. of Men for Process					
		1 Court	2 Courts	3 Courts	4 Courts	6 Courts
1. Site set up/surface preparation	2	1	2	2	3	4
2. Adhesive/base mat	5	0.5	2	3	4	6
3. 1st WB Mat Sealer	2	0.5				
4. 2nd WB Mat Sealer	2	0.5	2	2	3	4
5. Polyvac Sand/Vacuum	2	0.5				
6. 1st Filler Coat	2	0.5	1	2	2	3
7. 2nd Filler Coat	2	0.5				
8. Sand/Grind ridges	2	0.5	1	1	1	2
9. 1st Topcoat play area	2	0.5	1	2	2	3
10. 2nd Topcoat play area	2	0.5				
11. 1st Topcoat surround	2	1	2	2	3	3
12. 2nd Topcoat surround	2	1				
13. Line-marking	3	0.5	1	2	2	3
14. Site Clean up (progressive)	1	0.5				
<b>Sub Total days</b>		<b>8.5</b>	<b>12</b>	<b>16</b>	<b>20</b>	<b>28</b>
Number of man days						
25% bad weather allowance						
<b>Total man days</b>						